JOB NUMBER

OWNER'S RESIDENCE

PROJECT ADDRESS

LONGVIEW, TEXAS Ⓑ

GUIDELINES AND KEYNOTES

Ⓐ	ALL SHEETS NEED TO BE NUMBERED ACCORDING TO DIGIPLAN STANDARDS SEE G1.0
Ⓑ	PROVIDE PROJECT NAME, STREET ADDRESS & LEGAL DESCRIPTION
Ⓒ	PROVIDE RESIDENTIAL COMPLIANCE CHECK, CODE REFERENCES
Ⓓ	PROVIDE TABLE OF CONTENTS OR SHEET INDEX
Ⓔ	PROVIDE THE SCALE USED ON EACH PAGE OR EACH DRAWING IF VARIES
Ⓕ	PROVIDE LEGEND ON EACH PAGE AS NECESSARY
Ⓖ	PROVIDE A PROJECT SUMMARY CONSISTING OF APPROX. S.F. ,ROOF S.F.
Ⓗ	PROVIDE ANY TYPICAL NOTES THAT APPLY TO THE PROJECT
Ⓙ	THIS IS USUALLY ONLY APPLICABLE WHEN DESIGNER IS A LICENSED DESIGN PROFESSIONAL, SUCH AS AN ARCHITECT OR ENGINEER.

SHEET INDEX Ⓓ Ⓐ

GENERAL:

G1.0	COVER SHEET

CIVIL:

C1.0	PLOT PLAN, AND TYPICAL DETAILS

FOUNDATION:

S1.0	FOUNDATION PLAN & DETAILS

ARCHITECTURAL:

A1.0	OVERALL FLOOR PLAN
A2.0	ELEVATIONS AND SECTIONS

ELECTRICAL:

E1.0	ELECTRICAL PLAN

SHEET REFERENCE PREFIX

DISCIPLINE/TRADE	REFERENCE PREFIX
ARCHITECTURAL	A
CIVIL	C
DEMOLITION	D
ELECTRICAL	E
FIRE	F
GENERAL	G
LANDSCAPE	L
MECHANICAL	M
PLUMBING	P
STRUCTURAL	S
ZONING	Z

PDF FORMATS

PDF VERSIONS 1.x TO 2.0	PDF
PDF/A VERSIONS 1,2, AND 3	PDFA
XLM FORMS DATA FORMAT	XFDF
FORMS DATA FORMAT	FDF

PROJECT DIRECTORY

OWNER OWNER INFORMATION	**ARCHITECT** ARCHITECT OR DESIGNER INFORMATION (IF APPLICABLE)	**ELECTRIC UTILITY**
GAS UTILITY	**WATER & SEWER** CITY OF LONGVIEW, TEXAS	**CONTRACTOR** (IF APPLICABLE)

PROJECT SUMMARY Ⓖ

REGULATORY

LEGAL JURISDICTION: CITY OF LONGVIEW, TEXAS

BUILDING INFORMATION

AIR CONDITIONED AREA:	APPROX 1900 SQUARE FEET
GARAGE AREA:	APPROX 500 SQUARE FEET
FRONT AND BACK PORCH AREA	APPROX 270 SQUARE FEET
TOTAL AREA UNDER ROOF:	APPROX 2670 SQUARE FEET

CODE REFERENCE

2015 INTERNATIONAL ENERGY CODE (IECC)
2012 INTERNATIONAL RESIDENTIAL CODE (IRC)
2012 INTERNATIONAL PLUMBING CODE (IPC)
2012 INTERNATIONAL MECHANICAL CODE (IMC)
2012 INTERNATIONAL FIRE CODE (IFC)
2017 NATIONAL ELECTRIC CODE (NEC)

GENERAL DRAWING SYSTEMS Ⓕ



ROOMNAME
???
ROOM NAME / NUMBER
TYP
SIM
X/X7.1
ELEVATION NUMBER/ SHEET NUMBER
X'-X"
CEILING HEIGHT
X
X6.1
BLDG. SECTION NUMBER
BLDG. SECTION SHEET
WALL SECTION NUMBER
WALL SECTION SHEET
DETAIL NUMBER
DETAIL SHEET
LEADER TO DETAIL BUBBLE
0'-0"
ELEV
BLDG. HEIGHT REFERENCE POINT
XXXA
DOOR NUMBER
WINDOW LETTER
KEY NOTE
EQUIPMENT NUMBER
INTERIOR PARTITION
A
COLUMN NUMBER / LETTER
1
REVISION NUMBER / LETTER

REFER TO STRUCTURAL, MECHANICAL, PLUMBING AND ELECTRICAL SHEETS FOR SPECIFIC SYMBOLS

PROJECT GENERAL NOTES Ⓗ

1. PROVIDE FULL TERMITE TREATMENT UNDER FOUNDATION AND APPLIED TO NON-TREATED LUMBER TO 3' ABOVE FINISH FLOOR

SUPPORTING DOCUMENTATION

PROVIDE THE FOLLOWING MINIMAL DOCUMENTATION TO SUPPORT PLANS. THESE SHALL ALSO BE SUBMITTED PER SUBMITTAL STANDARD

1. APPLICATION
   (https://longviewtexas.gov/2824/PermitApplications)
2. DEVELOPMENT PERMIT
   (https://longviewtexas.gov/DocumentCenter/View/1152/Development-Permit-Application)
3. RESCHECK
   (https://energycode.pnl.gov/REScheckWeb/#/login)

CITY OF LONGVIEW STAMPS

COMPANY NAME
COMPANY ADDRESS
ADDRESS LINE 2
COMPANY PHONE/FAX
Ⓛ
COMPANY LOGO
OR OTHER

PROFESSIONAL
SEAL IF REQUIRED
00/00/0000

OWNER'S RESIDENCE Ⓑ
PROJECT ADDRESS
LONGVIEW, TEXAS

REVISIONS

NO.	DESCRIPTION	BY	DATE
1	FIRST REVISION DESCRIPTION	INTIAL	00/00/0000

COVER SHEET

PROJECT STATUS

Ⓔ

JOB NO: JOB NUMBER	DRAWN BY:	SHEET NO.: G1.0 Ⓐ
	CHECKED BY:	
ISSUE DATE: Issue Date	APPROVED BY: SCALE:	REVISION NO.: 1

Filename:F:\Land Development\2002\2002-094 Template Exhibits\CAD\ARCHITECTURAL\2002-094 - Arch.rvt

CITY OF LONGVIEW UNITED DEVELOPMENT CODE
SECTION 5. FLOOD DAMAGE PREVENTION
5.04. DRAINAGE AND STORMWATER CONTROL
FIGURE 40. LOT GRADING TYPES A,B, AND C. (C)


PROTECTIVE REAR SLOPE 1% MIN 10% MAX
REAR SLOPE
REAR SWALES
1% MIN
10% MAX
10'
SIDE SLOPE
SIDE SWALE
1% MIN
PROTECTIVE FRONT SLOPE
1% MIN
10% MAX
SEWER
PARKWAY SLOPE
2% MIN
STREET
SIDE SWALE
PROTECTIVE REAR SLOPE
1% MIN
10% MAX
SIDE SLOPE
SIDE SWALE
PROTECTIVE FRONT SLOPE
1% MIN
10% MAX
SEWER
PROTECTIVE SLOPE
2%
STREET
PROTECTIVE REAR SLOPE 1% MIN 10% MAX
PROTECTIVE FRONT SLOPE 1% MIN 10% MAX
1% MIN
SIDE SLOPE
1% MIN
SIDE SWALE
FRONT SWALE
FRONT SLOPE
1% MIN
10% MAX
SEWER
PROTECTIVE SLOPE
2% MIN
STREET

LOT GRADING TYPE A
ALL DRAINAGE TO STREET

LOT GRADING TYPE B
DRAINAGE TO FRONT AND REAR LOT LINE

LOT GRADING TYPE C
ALL DRAINAGE TO REAR LOT LINE

Table 42. Residential Driveway Standards



Residential Driveways			
		Minimum	Maximum
Local Residential Streets	Driveway Width	12 feet	30 feet
	Curb Cut	22 feet	40 feet
	Return Radius	5 feet	10 feet
Collector Streets	Driveway Width	12 feet	30 feet
	Curb Cut	22 feet	40 feet
	Return Radius	8 feet	10 feet
Arterial Streets	Driveway Width	16 feet	24 feet
	Curb Cut	40 Feet (Minor Arterials) 56 Feet (Principal Arterial)	64 feet
	Return Radius	12 Feet (Minor Arterial) 20 Feet (Principal Arterial)	20 Feet


LOT 14 BLOCK 2
SURVEY
D
LOT 11 BLOCK 2
SURVEY
4'-0"
G
4' WIDE
CONCRETE
SIDEWALK
PROPERTY BOUNDARY
10'-0"
(6' MIN.)
H
10'-6"
J
13'-9"
J
15'-0" GAS
PIPELINE EASEMENT
25'-0" STREET B
CENTERLINE
20'-0"
(20' MIN.)
LOT 12 BLOCK 2
SURVEY
D
C
NOTE: GRADE LOT
ACCORDING TO CITY OF
LONGVIEW GRADING TYPE "A".
ALL DRAINAGE TO STREET
A
PROPOSED 1 STORY RESIDENCE
H
STREET B
RIGHT OF WAY
5'-0" UTILITY
EASEMENT
G
H
10'-0"
SETBACK
F
BUILDING SETBACK LINE
D
LOT 13
BLOCK 2
EXISTING
SANITARY AND
WATER SERVICE
F
20'-0"
20'-0" BLDG.
SETBACK
5'-0"
EASEMENT
CO
WM
G
RIGHT OF WAY
8" W
8" W
4'-0"
R 4'-6"
25'-0" STREET A
CENTERLINE
GUTTER LINE
FACE OF CURB
BACK OF CURB
STREET A
26'-0"
CURB CUT
4' WIDE
CONCRETE
SIDEWALK
G
NOTE: CUT AND APRON SHALL
COMPLY WITH CITY OF LONGVIEW
DRIVEWAY AT ASPHALT STREET
B

(E)

N 1 PLOT PLAN EXAMPLE

SCALE: 1" = 10'-0" (K)


PLAN VIEW
SECTION A-A
VARIES (12' MIN - 30' MAX)
EXPANSION JOINT
CLASS P CONCRETE
CITY OF LONGVIEW ROW
ROW
END OF DRIVEWAY APRON OR DUMMY JOINT IN SIDEWALK (TYP)
ELEVATION LEVEL WITH TOP OF STREET CURB
TAPERED CURB BEYOND
TOP OF SIDEWALK
ROAD SURFACE
DRIVEWAY TRANSITION
EXPANSION JOINT WITH 3/4" SMOOTH DOWEL BARS @ 12" OC AT CONCRETE PAVEMENT
REFER TO CITY OF LONGVIEW STANDARD DETAILS FOR PAVEMENT THICKNESS
7" THICKENED EDGE
#3 REBAR @ 18" OCEW
ASPHALT STREET PAVEMENT - END OF DRIVEWAY
CONCRETE STREET PAVEMENT - EXPANSION JOINT WITH DOWEL BARS PER STANDARD DETAILS
3' (2% OR LESS CROSS SLOPE)
SLOPE AND LENGTH VARIES TO MATCH EXISTING GRADE (1/12 MAX)

NOTES:

1. WHEN CONNECTING TO EXISTING CURB AND GUTTER: SAWCUT AND REMOVE EXISTING CURB AND GUTTER TO THE LIMITS REQUIRED BY THE CITY OF LONGVIEW. CONSTRUCT CURB AND GUTTER EXPANSION JOINTS PER CITY OF LONGVIEW STANDARD AT EACH CURB AND GUTTER TIE - IN.
2. FOR NEW CURB AND GUTTER AT NEW DRIVEWAY, INSTALL EXPANSION JOINT IN CURB AND GUTTER AT END OF EACH DRIVEWAY FLARE OR AS APPROVED BY THE CITY OF LONGVIEW.
3. CONCRETE THICKNESS SHOWN IS FOR RESIDENTIAL DRIVEWAYS. COMMERCIAL DRIVEWAYS SHALL HAVE A MINIMUM THICKNESS OF 6".

	STREETS LATEST REVISION: 7/29/2020	CITY OF LONGVIEW, TEXAS STANDARD DETAILS	CONCRETE DRIVEWAY

\\ksa-server3\P Drive\Projects\LV350\00.07 CAD\02 Project\30 Sheets\LV350 - C - DT - ST - PVMT - DWAY - CONC.dwg

(B)


VARIES (12' MIN - 30' MAX)
A
INSTALL MINIMUM 2' WIDE DRIVEWAY ASPHALT TRANSITION SECTION WHEN CONNECTING TO ASPHALT OR GRAVEL DRIVEWAYS ONLY
7" THICKENED EDGE
INSTALL EXPANSION JOINT WHEN CONNECTING TO CONCRETE DRIVEWAYS ONLY
CITY OF LONGVIEW ROW
ROW
CLASS P CONCRETE
EXPANSION JOINT
NOTE 1
5' MINIMUM UNLESS OTHERWISE APPROVED BY THE CITY OF LONGVIEW (TYP)
24" CURB AND GUTTER
FLOW LINE OF GUTTER
#3 REBAR @18" OCEW
PLAN VIEW
TAPERED CURB BEYOND
REFER TO CITY OF LONGVIEW STANDARD DETAILS FOR PAVEMENT THICKNESS
ROAD SURFACE
ELEVATION LEVEL WITH TOP OF STREET CURB
TAPERED CURB
3' ADA PATH
5"
DRIVEWAY TRANSITION
7" THICKENED EDGE
#3 REBAR @ 18" OCEW
SECTION A-A

NOTES:

1. WHEN CONNECTING TO EXISTING CURB AND GUTTER: SAWCUT AND REMOVE EXISTING CURB AND GUTTER TO THE LIMITS REQUIRED BY THE CITY OF LONGVIEW. CONSTRUCT CURB AND GUTTER EXPANSION JOINTS PER CITY OF LONGVIEW STANDARD AT EACH CURB AND GUTTER TIE - IN.
2. FOR NEW CURB AND GUTTER AT NEW DRIVEWAY, INSTALL EXPANSION JOINT IN CURB AND GUTTER AT 5 FEET FROM END OF EACH DRIVEWAY CURB RETURN OR AS APPROVED BY THE CITY OF LONGVIEW.
3. CONCRETE THICKNESS SHOWN IS FOR RESIDENTIAL DRIVEWAYS. COMMERCIAL DRIVEWAYS SHALL HAVE A MINIMUM THICKNESS OF 5.5".
4. RESIDENTIAL LOCAL - MIN RADIUS = 5', MAX = 10'. RESIDENTIAL COLLECTOR - MIN RADIUS 8', MAX RADIUS 10'.
5. MAX CURB CUT: LOCAL = 40', COLLECTOR = 46'

	STREETS LATEST REVISION: 3/20/2018	CITY OF LONGVIEW, TEXAS STANDARD DETAILS	CONCRETE DRIVEWAY AT ASPHALT STREET

STREETS
STANDARD DETAILS

\\ksa-server3\P Drive\Projects\LV350\00.07 CAD\02 Project\30 Sheets\LV350 - C - DT - ST - PVMT - DWAY - CONC AT ASPH RD.dwg

CITY OF LONGVIEW
DEVELOPMENT SERVICES

PAGE 23 OF 26

(B)


VARIES (12' MIN - 30' MAX)
A
INSTALL MINIMUM 2' WIDE DRIVEWAY ASPHALT TRANSITION SECTION WHEN CONNECTING TO ASPHALT OR GRAVEL DRIVEWAYS ONLY
7" THICKENED EDGE
INSTALL EXPANSION JOINT WHEN CONNECTING TO CONCRETE DRIVEWAYS ONLY
CITY OF LONGVIEW ROW
ROW
CLASS P CONCRETE
EXPANSION JOINT
3' (MIN)
PROVIDE SAW CONTRACTION JOINTS AS REQUIRED
SIDEWALK WIDTH VARIES 4' (TYP)
MONOLITHIC CURB TYPICAL STANDARD 24" CURB AND GUTTER ONLY IF APPROVED BY THE CITY OF LONGVIEW
FLOW LINE OF GUTTER
#3 REBAR @ 18" OCEW
SAWCUT OR BLOCKOUT LINE SEE NOTES
PLAN VIEW
TAPERED CURB BEYOND
REFER TO CITY OF LONGVIEW STANDARD DETAILS FOR PAVEMENT THICKNESS
ROAD SURFACE
ELEVATION LEVEL WITH TOP OF STREET CURB
TAPERED CURB
3' ADA PATH
5"
DRIVEWAY TRANSITION
7" THICKENED EDGE
#3 REBAR @ 18" OCEW
SECTION A-A

NOTES:

1. EXISTING PAVEMENT - SAWCUT AND REMOVE EXISTING CONCRETE PAVEMENT AND CURB AND GUTTER AT BLOCKOUT LINE.
2. NEW PAVEMENT - CONSTRUCT NEW PAVEMENT TO BLOCKOUT LINE.
3. CONSTRUCTION EXPANSION JOINT AT SAWCUT/BLOCKOUT LINE AT PAVEMENT WITH SMOOTH DOWEL BARS AT 12" OC. DRILL AND EPOXY INTO EXISTING PAVEMENT. GREASE AND INSTALL GREASE CAP IN DRIVEWAY CONCRETE.
4. CONSTRUCT CURB AND GUTTER EXPANSION JOINT WITH TWO #4 SMOOTH BARS CENTERED IN GUTTER.
5. REFER TO CITY OF LONGVIEW STANDARD DETAILS FOR EXPANSION JOINTS AND SEALING.
6. CONCRETE THICKNESS SHOWN IS FOR RESIDENTIAL DRIVEWAYS. COMMERCIAL DRIVEWAYS SHALL HAVE A MINIMUM THICKNESS OF 5.5".
7. CONCRETE DRIVEWAY APRONS ARE REQUIRED AT ALL CONCRETE STREET.
8. RESIDENTIAL LOCAL - MIN RADIUS = 5', MAX = 10'. RESIDENTIAL COLLECTOR - MIN RADIUS 8', MAX RADIUS 10'.
9. MAX CURB CUT: LOCAL = 40', COLLECTOR = 46'

	STREETS LATEST REVISION: 3/21/2018	CITY OF LONGVIEW, TEXAS STANDARD DETAILS	CONCRETE DRIVEWAY AT CONCRETE STREET

STREETS
STANDARD DETAILS

\\ksa-server3\P Drive\Projects\LV350\00.07 CAD\02 Project\30 Sheets\LV350 - C - DT - ST - PVMT - DWAY - CONC AT CONC RD.dwg

CITY OF LONGVIEW
DEVELOPMENT SERVICES

PAGE 22 OF 26

GENERAL NOTES

1. EXCEPT AS NOTED, BUILDING PAD GRADING TO BE PREFORMED BY HOUSE CONTRACTOR AFTER COMPLETION OF SUBDIVISION IMPROVEMENTS
2. ALL FINISH FLOOR ELEVATION SHALL BE MINIUMUM OF 8" ABOVE THE HIGHEST GRADE ADJAVENT TO THE BUILDING PAD. SEE CURRENT BUILDING CODE. FLOOR ELEVATIONS SHOWN ARE BASED ON THE MINUMUM FRONT SETBACK. ALL GRADING TYPE A & B LOT FINISH FLOORS SHALL BE AT LEAST 1 FEET ABOVE THE ROAD CROWN ALONG LOT FRONTAGE.
3. DRIVEWAY SLOPES BREAKS SHALL NOT EXCEED AN ALGEBRAIC DIFFERENCE OF +/- 14% WITHOUT PROPER VERTICAL CURVE.
4. MEANDER SWALES AROUND SPECIMEN TREES AND DO NOT DISTURB WETLAND VEGETATION.
5. BUILDINGS SHALL NOT BE BUILT WITHIN 100 FEET OF AN OIL WELL OR WITHIN 50 FEET OF A TANK BATTERY DIKE.
6. HYDRANTS SHALL NOT BE GREATER THAN 600 FEET ANY EXTERIOR PORTION OF THE BUILDING AT GROUND LEVEL MEASURED AS THE HOSE IS LAYED AS APPROVED BY THE FIRE CODE OFFICAL. A FIRE HYDRANT SHALL BE WITHIN 250 FEET OF ANY POINT ON THE STREET OR ROAD FRONTAGE TO THE PROPERTY.

LEGEND (L)

PROPERTY LINE	———————
UTILITY EASEMENT LINE	- - - - - - - - -
SETBACK LINE	— — — — — —
STREET CENTER LINE	—— – —— – ——
GAS LINE	—— G —— G ——
WATER LINE	—— 8"W —— 8"W ——

GUIDELINES & KEYNOTES

(A)	NUMBER OF STORIES
(B)	DRIVEWAY SPECS PER CITY REQUIREMENTS
(C)	LOT DRAINAGE PER CITY REQUIREMENTS
(D)	PROVIDE PROJECT NAME, STREET ADDRESS & LEGAL DESCRIPTION
(E)	NORTH ARROW
(F)	TWO PARKING SPACES PER CITY REQUIREMENTS
(G)	SIDEWALK
(H)	SET BACKS, EASEMENTS AND , IF APPLICABLE, FEMA FLOOD BOUNDARIES - ALL DIMENSIONED
(J)	LOCATION OF PROPOSED STRUCTURE
(K)	PROVIDE THE SCALE USED ON EACH PAGE OR EACH DRAWING IF VARIES
(L)	LEGEND EXPLAINING WHAT THE LINES ARE AND WHAT THE DRAWING REPRESENTS

CITY OF LONGVIEW STAMPS

COMPANY NAME
COMPANY ADDRESS
ADDRESS LINE 2
COMPANY PHONE/FAX

COMPANY LOGO
OR OTHER

PROFESSIONAL
SEAL IF REQUIRED
00/00/0000

OWNER'S RESIDENCE
PROJECT ADDRESS
LONGVIEW,TEXAS (D)

REVISIONS

NO.	DESCRIPTION	BY	DATE
1	FIRST REVISION DESCRIPTION	INTIAL	00/00/0000

PLOT PLAN, AND TYPICAL DETAILS

PROJECT STATUS

JOB NO: JOB NUMBER	ISSUE DATE: Issue Date
DRAWN BY: CHECKED BY: APPROVED BY:	SCALE: As indicated
SHEET NO: C1.0	REVISION NO: 1

Filename:F:\Land Development\2002\2002-094 Template Exhibits\CAD\ARCHITECTURAL\2002-094 - Arch.rvt

WINDOW SCHEDULE

MARK	GANG	SIZE	DESCRIPTION	HEAD HEIGHT	REMARKS
A	2	3'-0"x6'-0"	SINGLE HUNG VINYL	8'-0"	
B	1	3'-0"x6'-0"	SINGLE HUNG VINYL	8'-0"	EGRESS SASH OPENING = 29"x29" MIN. Ⓒ
C	1	6'-0"x6'-0"	FIXED VINYL	8'-0"	
D	1	3'-0"x3'-6"	SINGLE VINYL SLIDER	8'-0"	
E	1	3'-0"x4'-0"	SINGLE HUNG VINYL	8'-0"	

Ⓓ NOTE: SEE IRC R308.4.2, R308.4.3, R308.4.5 FOR TEMPERED GLASS LOCATIONS

DOOR SCHEDULE

MARK	SIZE	DESCRIPTION
A	3'-0"x8'-0"	3068 EXTERIOR ENTRY DOOR W/ TRANSOM
B	2'-8"x6'-8"	SOLID CORE OR HONEYCOMB STEEL DOOR, 20 MIN. RATING W/ SELF CLOSING DEVICE
C	2'-6"x6'-8"	INTERIOR 5 PANEL DOOR
D	2'-4"x6'-8"	INTERIOR 5 PANEL DOOR
E	4'-0"x6'-8"	INTERIOR 5 PANEL DOUBLE
F	4'-0"x5'-0"	A/C CLOSET
G	16'-0"x8'-0"	SECTIONAL OVERHEAD DOOR

Ⓓ NOTE: GLASS IN ALL DOORS MUST BE TEMPERED

RESIDENTIAL FLOOR PLAN GUIDELINES AND KEYNOTES

A1	SHOW DIMENSIONS OF OVERALL BUILDING
A2	SHOW DIMENSIONS OF BUILDING OFFSETS
A3	SHOW DIMENSIONS OF ALL OPENINGS IN THE EXTERIOR WALLS
A4	SHOW DIMENSIONS TO ALL INTERIOR WALLS
Ⓑ	LEGEND EXPLAINING WHAT THE LINES ARE AND WHAT THE DRAWING REPRESENTS
Ⓒ	FOR WINDOWS USED IN BEDROOMS, CALL OUT THE MINIMUM SIZE OPENING OF EMERGENCY EGRESS. SEE IRC R310 FOR MINIMUM REQUIREMENTS. ASK MANUFACTURER FOR ACTUAL OPENING SIZE.
Ⓓ	INDICATE LOCATIONS WHERE TEMPERED GLASS IS REQUIRED PER R308.4.2, R308.4.3, R308.4.5
Ⓔ	INDICATE LOCATIONS OF HOSE BIBS
Ⓕ	INDICATE LOCATIONS OF GAS METERS. MUST MAINTAIN A 3' CLEARANCE FROM ANY OPERABLE DOOR OR WINDOW
Ⓖ	INDICATE LOCATION OF H.V.A.C. (HEATING AND AIR CONDITIONING) CONDENSER
Ⓗ	LABEL ALL ROOMS AND AREAS INSIDE THE HOUSE
Ⓘ	INDICATE LOCATIONS OF AIR CONDITIONER IN A SPACE NOT LESS THAN 3'x3'
Ⓙ	INDICATE LOCATIONS OF WATER HEATER AND ACCESSORIES
Ⓚ	IRC R302.6 REQUIRES FIRE SEPARATION WALL AND CEILING BETWEEN GARAGE AND REST OF THE HOUSE, ALSO SEE IRC R302.5 FOR DOOR
Ⓛ	OPTIONAL NOTES DEFINING ENERGY PERFORMANCE
Ⓜ	INDICATE LOCATIONS OF ELECTRIC METERS, & CIRCUIT BREAKER PANELS - LOCATE ON EXTERIOR OF BUILDING IF NO MAIN DISCONNECT IS PROVIDED

LEGEND Ⓑ

◇ X	WINDOW TAG, SEE WINDOW SCHEDULE OR SHOW WINDOW SIZE ON THE PLAN Ⓚ
XXX	DOOR TAG, SEE DOOR SCHEDULE OR SHOW DOOR SIZE ON THE PLAN Ⓚ
X / XX.X SIM	SECTION TAG, SEE REFERENCED SHEET
XXX / 0'-0"	BUILDING HEIGHT REFERENCE POINT
▨	BRICK VENEER ON 2X4 WOOD STUD
▭	HORIZONTAL WOOD SIDING ON 2X4 WOOD STUD 1/2" GYP. BOARD ON INTERIOR FACE
▭	INTERIOR 2X4 WOOD STUD PARTITION (2X6 @ PLUMBING WALLS) 1/2" GYP. BOARD ON EACH FACE
▭	WALLS THAT MAKE UP THE THERMAL ENVELOPE INCLUDING DOORS & WINDOWS IN THESE WALLS
	CABINETS OR SHELVES (UPPERS DASHED)
H.B.	HOSE BIB

BUILDING GENERAL NOTES Ⓛ

1. ALL CONSTRUCTION SHALL COMPLY WITH THE 2012 INTERNATIONAL RESIDENTIAL CODE (IRC)
2. THESE DRAWINGS DO NOT CONTAIN COMPLETE SPECIFICATIONS, DETAILS AND INFORMATION REQUIRED FOR THE INTERIOR FINISHES OF THE PROJECT. ADDITIONAL INFORMATION SHALL BE OBTAINED FROM THE OWNER.
3. ALL MECHANICAL WORK SUCH AS, BUT NOT LIMITED TO ELECTRICAL, PLUMBING, HEATING, AIR CONDITIONING, VENTILATING, ETC., ARE TO BE ESTABLISHED AND DESIGNED BY LICENSED TRADESMEN ACCEPTABLE TO THE CITY OF LONGVIEW FOR THE RESPECTIVE WORK . ALL HVAC EQUIPMENT AND DUCTWORK SHALL COMPLY WITH APPLICABLE STATE, NATIONAL AND LOCAL CODES
4. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES REQUIRED FOR SAFE EXECUTION AND COMPLETION OF WORK, AND FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK.
5. ANY ERRORS, OMISSIONS OR INCONSISTENCIES ON THESE DRAWINGS OR ANY VARIATIONS OR AMBIGUITIES BETWEEN THESE DRAWINGS AND ACTUAL SITE AND CONSTRUCTION CONDITIONS AND/OR REQUIREMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER FOR RESOLUTION PRIOR TO CONSTRUCTION.
7. CONTRACTOR SHALL VERIFY ALL DIMENSIONS. DO NOT SCALE DRAWINGS. NOTIFY OWNER OR DESIGNER OF ANY DISCREPANCIES FOR RESOLUTION PRIOR TO CONSTRUCTION.
8. CONTRACTOR SHALL COORDINATE HIS WORK WITH ALL OTHER TRADES.
9. WATER RESISTANT GYPSUM BACKER BOARD SHALL BE USED WITH BATHTUB AND SHOWER SURROUNDS.
10. CAULK ALL EXTERIOR JOINTS AROUND WINDOWS AND DOOR FRAMES, BETWEEN WALL CAVITIES AND WINDOW OR DOOR FRAMES, BETWEEN WALL AND FOUNDATION, BETWEEN WALL AND ROOF, BETWEEN WALL PANELS AND ALL PENETRATIONS OR UTILITIES THROUGH WALLS AND ROOFS.

THERMAL ENVELOPE NOTES

Ⓛ

1. THE CONSTRUCTION DRAWINGS AND ASSOCIATED DOCUMENTS DEMONSTRATE ENERGY CODE COMPLIANCE FOR THE GENERAL ENVELOPE. THE PLAN OF THE THERMAL ENVELOPE IS INDICATED ON THE FLOOR PLAN.
2. AIR BARRIERS AND THERMAL BARRIERS SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS.
3. FENESTRATION SHALL BE LISTED AND LABELED AS MEETING AAMA/WDMA/CSA 101/I.S.2/A440 OR HAVE INFILTRATION RATES PER NFRC 400 THAT DOES NOT EXCEED CODE LIMITS.
4. AUTOMATIC OR GRAVITY DAMPERS SHALL BE INSTALLED ON ALL OUTDOOR AIR INTAKES AND EXHAUSTS.
5. U-FACTORS OF FENESTRATION PRODUCTS SHALL BE IN ACCORDANCE WITH NFRC TEST PROCEDURES OR TAKEN FROM THE DEFAULT TABLE.
6. ALL INSTALLED INSULATION SHALL BE LABELED OR THE INSTALLED R-VALUES PROVIDED.
7. ROOF AND/OR CEILING INSULATION SYSTEMS SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS AND MARKED EVERY 300 SQUARE FEET.
8. VENTED ATTICS WITH AIR PERMEABLE INSULATION SHALL INCLUDE BAFFLES ADJACENT TO SOFFIT AND EAVE VENTS THAT EXTEND OVER THE INSULATION.
9. ATTIC ACCESS HATCHES AND DOOR INSULATION SHALL BE A GREATER R-VALUE OF THE ADJACENT CEILING.


82'-1" A1 TYP.
5 1/2"
17'-0"
6'-4"
6'-8" A2
19'-0"
10'-0"
5'-3 1/2"
17'-4"
4'-0"
4'-0"
4'-0"
3'-6"
12'-0"
3'-6"
5'-0"
5'-0"
5'-6" A3
5'-6" A3
PORCH POST
HVAC CONDENSER ON 4" CONC. PAD
PRE-MANUFACTURED STEEL FIRE PLACE
4'-0"
2'-4"
HEARTH
MANTEL
9'-7"
H.B.
E
3'-0"
Washer
Dryer
5 1/2"
5'-8"
MASTER BEDROOM H TYPICAL
DRESSING
CLO.
GUEST
CAB.
LIVING ROOM
LINE OF VAULTED CEILING ABOVE
LAUNDRY
STORE ROOM
11'-0"
2'-8"
PANTRY
15" SHELVING
3'-0"
A/C
W/H
2'-4"
3'-4"
5'-8" A4
2'-0"
18" SHELF & ROD
2'-5"
REF.
FIRE SEPARATION WALL BETWEEN GARAGE AND REST OF HOUSE K
MAIN DISCONNECT (MUST BE PROVIDED WHEN BREAKER PANEL IS LOCATED ON THE INTERIOR
BREAKER PANEL
ELECTRIC METER
M
ATTIC ACCESS ABOVE
7'-0"
33'-8" A1 TYP.
3'-8 1/2" A4
12'-0"
RANGE
GARAGE H TYPICAL
8'-8"
22'-8"
5 1/2"
5'-4"
BATH
BEDROOM 3
BEDROOM 2
12" SHELF & ROD
STUDY H TYPICAL
DW
DRESSING
5'-6 1/2"
5'-6"
6 A2.0
LINE OF GARAGE DOOR
COVERED PORCH
H.B. E
30'-7"
29'-8"
14'-4"
4'-0"
11'-4"
3'-6 1/2"
GAS METER
3'-0" CLR. MIN.
SEE PLOT PLAN FOR SIDEWALK
SEE PLOT PLAN FOR DRIVEWAY
5'-11 1/2"
5'-8 1/2"
6'-0" A3
6'-0" A3
5'-6"
5'-6"
11'-8"
6'-4" A4
12'-0"
3'-0"
11'-0"
5'-0"
5'-0"
5'-0"
3'-3 1/2"
16'-0"
3'-4"
44'-0"
15'-0"
22'-7 1/2" A2
82'-1"

1 FLOOR PLAN EXAMPLE

SCALE: 1/4" = 1'-0"

COMPANY NAME
COMPANY ADDRESS
ADDRESS LINE 2
COMPANY PHONE/FAX

COMPANY LOGO
OR OTHER

PROFESSIONAL
SEAL IF REQUIRED

00/00/0000

OWNER'S RESIDENCE
PROJECT ADDRESS
LONGVIEW,TEXAS

REVISIONS

NO.	DESCRIPTION	BY	DATE
1	FIRST REVISION DESCRIPTION	INTIAL	00/00/0000

OVERALL FLOOR PLAN

PROJECT STATUS

CITY OF LONGVIEW STAMPS

JOB NO: JOB NUMBER	ISSUE DATE: Issue Date
DRAWN BY: / CHECKED BY: / APPROVED BY:	SCALE: 1/4" = 1'-0"
SHEET NO.: A1.0	REVISION NO: 1

Filename F:\Land Development\2002\2002-094 Template Exhibits\CAD\ARCHITECTURAL\2002-094 - Arch.rvt


PRE-MANUFACTURED STEEL CHIMNEY CAP
ASPHALT SHINGLES OVER UNDERLAYMENT
12"
6"
F
METAL GUTTER
TOP PLATE 10'-0"
HORIZONTAL WOOD SIDING
METAL LEADER & DOWNSPOUT
FINISH FLOOR 0'-0"
C
BRICK VENEER
H
B
WOOD POSTS
H.V.A.C. CONDENSER
E

1 REAR ELEVATION EXAMPLE
SCALE: 1/8" = 1'-0"


F
12"
6"
ASPHALT SHINGLES OVER UNDERLAYMENT
TOP PLATE 10'-0"
METAL DOWNSPOUT & LEADER
WOOD POST
HORIZONTAL WOOD SIDING
I
FINISH FLOOR 0'-0"
BRICK VENEER
HOSE BIB
B

2 SIDE ELEVATION EXAMPLE
SCALE: 1/8" = 1'-0" Ⓚ


ASPHALT SHINGLES OVER UNDERLAYMENT
F
12"
6"
HORIZONTAL WOOD SIDING
I
H
TOP PLATE 10'-0"
C
METAL GUTTER
METAL LEADER & DOWNSPOUT
FINISH FLOOR 0'-0"
BRICK VENEER
GAS METER
D
HOSE BIB
B
16'X8' SECTIONAL OVERHEAD DOOR

3 FRONT ELEVATION EXAMPLE
SCALE: 1/8" = 1'-0" Ⓚ


12"
6"
ASPHALT SHINGLES OVER UNDERLAYMENT
I
H
TOP PLATE 10'-0"
METAL GUTTER
METAL LEADER & DOWNSPOUT
FINISH FLOOR 0'-0"
ELECTRIC METER
D
HORIZONTAL WOOD SIDING

4 SIDE ELEVATION EXAMPLE
SCALE: 1/8" = 1'-0"


METAL GUTTER
PRE-MANUFACTURED STEEL CHIMNEY CAP
RIDGE
6" / 12"
F
CRICKET
VALLEY
HIP
RIDGE
METAL GUTTER
ASPHALT SHINGLES OVER UNDERLAYMENT
I

5 ROOF PLAN EXAMPLE
SCALE: 1/8" = 1'-0"


I
ASPHALT SHINGLES OVER UNDERLAYMENT
5/8" PLYWOOD DECK
F
12"
6"
G
SPRAY FOAM OR BATT INSULATION (R-38 MIN.)
TRUSS BEARING 11' - 0"
TOP PLATE 10'-0"
CONTINUOUS METAL FLASHING W/ DRIP EDGE
5/8" GYPSUM BOARD
1x6 FASCIA
1/2" GYPSUM BOARD
I
SOFFIT PANEL
R -13 BATT. INSULATION
J
1x4 FRIEZE
BRICK VENEER
2x4 WOOD STUD FRAMING @ 16" O.C.
MASONRY ANCHORS @ 16" O.C. EA. WAY, TYP.
BUILDING WRAP OVER 1/2" SHEATHING
1" RIGID INSULATION (R-5 MIN.)
J
WEEP HOLES @ 24" O.C.
ADD Z FLASHING BEHIND BRICK
TREATED 2x4 BOTTOM PLATE MECHANICALLY ANCHORED TO FOUNDATION @ 32" O.C. MAX.
SLOPE GRADE AWAY FROM BUILDING
FINISH FLOOR 0'-0"
TOP OF SLAB 0' - 0"
8" MIN.

6 TYPICAL WALL SECTION EXAMPLE
SCALE: 3/4" = 1'-0" Ⓚ

RESIDENTIAL GUIDELINES AND KEYNOTES

Ⓐ	LEGEND EXPLAINING WHAT THE LINES ARE AND WHAT THE DRAWING REPRESENTS
Ⓑ	INDICATE LOCATIONS OF HOSE BIBS
Ⓒ	FOR WINDOWS USED IN BEDROOMS, CALL OUT THE MINIMUM SIZE OPENING FOR EMERGENCY EGRESS. SEE IRC R310 FOR MINIMUM REQUIREMENTS. ASK MANUFACTURER FOR ACTUAL OPENING SIZE.
Ⓓ	INDICATE LOCATIONS OF GAS, ELECTRIC METERS AND CIRCUIT BREAKER PANELS
Ⓔ	INDICATE LOCATION OF H.V.A.C. (HEATING AND AIR CONDITIONING) CONDENSER
Ⓕ	INDICATE CRICKETS, RIDGES, HIPS & VALLEY LOCATIONS, AND ROOF SLOPES
Ⓖ	INDICATE REQUIRED ROOF INSULATION IN COMPLIANCE WITH CURRENT ENERGY CODES
Ⓗ	INDICATE HEIGHTS, AND OR LEVELS
Ⓘ	INDICATE DIFFERENT TYPES OF EXTERIOR MATERIALS USED
Ⓙ	INDICATE REQUIRED WALL INSULATION SYSTEM IN COMPLIANCE WITH CURRENT ENERGY CODES
Ⓚ	PROVIDE THE SCALE USED ON EACH PAGE OR EACH DRAWING IF VARIES

SYMBOL LEGEND Ⓐ

◇ X	WINDOW TAG, SEE WINDOW SCHEDULE
(XXX)	DOOR TAG, SEE DOOR SCHEDULE
X / XX.X SIM	SECTION TAG, SEE REFERENCED SHEET
XXX 0'-0"	BUILDING HEIGHT REFERENCE POINT

COMPANY NAME
COMPANY ADDRESS
ADDRESS LINE 2
COMPANY PHONE/FAX

COMPANY LOGO
OR OTHER

PROFESSIONAL
SEAL IF REQUIRED
00/00/0000

OWNER'S RESIDENCE
PROJECT ADDRESS
LONGVIEW, TEXAS

REVISIONS

NO.	DESCRIPTION	BY	DATE
1	FIRST REVISION DESCRIPTION	INTIAL	00/00/0000

ELEVATIONS AND SECTIONS

PROJECT STATUS

CITY OF LONGVIEW STAMPS

ISSUE DATE: Issue Date	SCALE: As indicated	REVISION NO: 1
JOB NO: JOB NUMBER	DRAWN BY:	SHEET NO.: A2.0
	CHECKED BY:	
	APPROVED BY:	

Filename:F:\Land Development\2002\2002-094 Template Exhibits\CAD\ARCHITECTURAL\2002-094 - Arch.rvt

GUIDELINES AND KEYNOTES

Ⓐ	LEGEND EXPLAINING WHAT THE LINES ARE AND WHAT THE DRAWING REPRESENTS
Ⓑ	INDICATE LOCATIONS OF OUTLETS, LIGHTS, FAN, AND PLUGS
Ⓒ	INDICATE LOCATIONS OF EXHAUST FANS
Ⓓ	INDICATE LOCATIONS OF SMOKE/ CARBON MONOXIDE DETECTORS
Ⓔ	INDICATE LOCATIONS OF GAS AND/ OR ELECTRIC METERS
Ⓕ	INDICATE LOCATION OF H.V.A.C. (HEATING AND AIR CONDITIONING) CONDENSER
Ⓖ	INDICATE LOCATION OF THE MAIN BREAKER PANEL - LOCATE ON EXTERIOR OF BUILDING IF NO MAIN DISCONNECT IS PROVIDED
Ⓗ	PROVIDE THE SCALE USED ON EACH PAGE OR EACH DRAWING IF VARIES
Ⓙ	PROVIDE GFCI/AFCI PROTECTION IN ACCORDANCE W/ ELECTRICAL CODE REQUIREMENTS
Ⓚ	PROVIDE ANY TYPICAL NOTES THAT APPLY TO THE PROJECT

BUILDING MECH, ELEC & PLBG NOTES

Ⓚ

1. ALL MECHANICAL WORK SUCH AS, BUT NOT LIMITED TO ELECTRICAL, PLUMBING, HEATING, AIR CONDITIONING, VENTILATING, ETC., ARE TO BE ESTABLISHED AND DESIGNED BY LICENSED TRADESMEN ACCEPTABLE TO THE CITY OF LONGVIEW FOR THE RESPECTIVE WORK . ALL HAVC EQUIPMENT AND DUCTWORK SHALL COMPLY WITH APPLICABLE STATE, NATIONAL AND LOCAL CODES
2. SMOKE DETECTORS SHALL BE AC POWERED WITH BATTERY BACK-UP AND U.L. APPROVED.
3. HEATING AND COOLING EQUIPMENT SHALL BE SIZED PER ACCA MANUAL S BASED ON LOADS CALCULATED PER ACCA MANUAL J OR OTHER METHODS APPROVED BY THE CODE OFFICIAL.
4. HVAC PIPING CONVEYING FLUIDS ABOVE 105°F OR CHILLED FLUIDS BELOW 55°F SHALL BE INSULATED R-3 MIN.
5. PROVIDE PROTECTION OF INSULATION ON HVAC PIPING.
6. CARBON MONOXIDE ALARMS SHALL BE INSTALLED OUTSIDE EACH SEPERATE SLEEPING ROOM IN THE IMMEDIATE VICINITY OF BEDROOM'S, IN DWELLING UNITS WITHIN WHICH FUEL-FIRED APPLIANCES ARE INSTALLED AND IN DWELLING UNITS THAT HAVE ATTACHED GARAGES. CARBON MONDOXIDE DETECTORS SHALL BE HARDWIRED.
7. DO NOT USE BUILDING CAVITIES AS DUCTS OR PLENUMS. ALL RETURN AIR SHALL BE DUCTED.
8. ALL DUCTS SHALL HAVE A TIGHTNESS TEST RESULT OF <=4 CFM/100 S.F. ACROSS THE SYSTEM OR<=3 CFM/100 S.F. WITHOUT AIR HANDLER @ 25 Pa. FOR ROUGH-IN TESTS, VERIFICATION MAY NEED TO OCCUR DURING FRAMING INSPECTION.
9. DUCTS SHALL BE PRESSURE TESTED TO DETERMINE AIR LEAKAGE WITH EITHER A ROUGH-IN TEST OR POST CONSTRUCTION TEST.
10. AIR HANDLER LEAKAGE SHALL BE DESIGNATED BY MANUFACTURER AT <= 2% OF DESIGN AIR FLOW.
11. INSTALL HEAT PUMP THERMOSTAT ON HEAT PUMPS.
12. 75% OF LAMPS IN PERMANENT LIGHT FIXTURES OR 75% OF PERMANENT LIGHT FIXTURES SHALL HAVE HIGH EFFICACY LAMPS EXCEPT FOR LOW VOLTAGE LIGHTING.
13. CIRCULATING SERVICE HOT WATER SYSTEM SHALL HAVE AUTOMATIC OR ACCESSIBLE MANUAL CONTROLS.
14. ALL MECHANICAL VENTILATION SYSTEM FANS NOT PART OF TESTED AND LISTED HVAC EQUIPMENT SHALL MEET EFFICACY AND AIR FLOW LIMITS.
15. HOT WATER BOILERS SUPPLYING HEAT THROUGH ONE OR TWO PIPE HEATING SYSTEMS SHALL HAVE OUTDOOR SETBACK CONTROLS TO LOWER BOILER WATER TEMPERATURE BASED ON OUTDOOR TEMPERATURE.
16. HETAED WATER CIRCULATION SYSTEMS SHALL HAVE A CIRCULATION PUMP. SYSTEM SHALL HAVE A DEDICATED RETURN PIPE OR A COLD WATER SUPPLY PIPE. CONTROLS FOR CIRCULATING HOT WATER SYSTEM SHALL START THE PUMP WITH SIGNAL FOR HOT WATER DEMAND WITHIN THE OCCUPANCY AND SHALL AUTOMATICALL TURN OFF PUMP WHEN WATER IN CIRCULATION LOOP IS AT SET-POINT TEMPERATURE AND NO DEMAND FOR HOT WATER EXISTS.
17. MANUFACTURER MANUALS FOR MECHANICAL AND WATER HEATING SYSTEMS SHALL BE PROVIDED.

SYMBOL LEGEND Ⓐ

◎	RECESSED LIGHT FIXTURE
⊕	LIGHT FIXTURE JUNCTION BOX
φ	RECEPTACLE
⏀	ABOVE COUNTER RECEPTACLE
φGFI	GFI RECEPTACLE
φR	220V RECEPTACLE
S	SINGLE POLE SWITCH
S3	3-WAY SWITCH
⊠	EXHAUST GRILL
SD	SMOKE DETECTOR
CO	CARBON MONOXIDE DETECTOR
SD/CO	COMBO UNIT
✻	CEILING FAN



HVAC CONDENSER ON 4" CONC. PAD
F
B
C
D
E
G
SD
SD/CO
GFI
3
A/C
W/H
WH
REF
RANGE
DW
Washer
Dryer
ATTIC LIGHT ABOVE
BREAKER PANEL
MAIN DISCONNECT (MUST BE PROVIDED WHEN BREAKER PANEL IS LOCATED ON THE INTERIOR
ELECTRIC METER
G.D.O.
GAS METER

1 ELECTRICAL PLAN EXAMPLE
SCALE: 1/4" = 1'-0" Ⓗ

CITY OF LONGVIEW STAMPS

COMPANY LOGO
OR OTHER

COMPANY NAME

COMPANY ADDRESS
ADDRESS LINE 2
COMPANY PHONE/FAX

PROFESSIONAL
SEAL IF REQUIRED
00/00/0000

OWNER'S RESIDENCE
PROJECT ADDRESS
LONGVIEW,TEXAS

REVISIONS

NO.	DESCRIPTION	BY	DATE
1	FIRST REVISION DESCRIPTION	INTAL	00/00/0000

ELECTRICAL PLAN

PROJECT STATUS

Ⓗ

JOB NO: JOB NUMBER
ISSUE DATE: Issue Date
DRAWN BY: CHECKED BY: APPROVED BY: SCALE: 1/4" = 1'-0"
SHEET NO: E1.0
REVISION NO: 1

Filename:F:\Land Development\2002\2002-094 Template Exhibits\CAD\ARCHITECTURAL\2002-094 - Arch.rvt


SLOPE OUTSIDE PAVEMENT AWAY FROM BUILDING
5 1/2"
1 1/2"
2" MAX.
FOR SLAB REINF. SEE PLAN
TOP OF SLAB 0'-0"
SEE PLAN
1'-6"
3" CLR.
3" CLR.
(2) #5 CONT. TOP & BOTTOM W/ #3 TIES @ 24" O.C.
1'-0"

2 GRADE BEAM AT MASONRY @ PAVEMENT EXAMPLE

SCALE: 1" = 1'-0"


SLOPE OUTSIDE GRADE AWAY FROM BUILDING
5 1/2"
1 1/2"
2" MAX.
FOR SLAB REINF. SEE PLAN
TOP OF SLAB 0'-0"
SEE PLAN
8" MIN.
1'-6"
3" CLR.
3" CLR.
(2) #5 CONT. TOP & BOTTOM W/ #3 TIES @ 24" O.C.
1'-0"

3 GRADE BEAM AT MASONRY @ GRADE EXAMPLE

SCALE: 1" = 1'-0"


EXTEND SLAB TO FACE OF GRADE BEAM
SLOPE OUTSIDE PAVEMENT AWAY FROM BUILDING
1 1/2"
2" MAX.
FOR SLAB REINF. SEE PLAN
TOP OF SLAB 0'-0"
SEE PLAN
1'-6"
3" CLR.
3" CLR.
(2) #5 CONT. TOP & BOTTOM W/ #3 TIES @ 24" O.C.
1'-0"

4 GRADE BEAM @ PAVEMENT EXAMPLE

SCALE: 1" = 1'-0"


49'-5 1/2"
21'-7 1/2"
11'-0"
23'-9 1/2"
6'-8" E TYP.
7'-10"
3'-4"
7'-10"
5 S1.0
5 S1.0
5 S1.0
3 S1.0
5 S1.0
5 S1.0 SIM.
5 S1.0
4 S1.0
12x18
SLOPE 1% MIN.
9'-7"
2'-0 1/2"
-1 1/2"
6 1/2"
13'-11 3/4"
31'-1 1/2"
30'-7"
4'-11 1/2"
11'-7 3/4"
C 4" CONCRETE SLAB OVER VAPOR BARRIER W/ 6"x6"-6-6 WWF
D
9'-9"
7 S1.0
7 S1.0 D
33'-8"
3 S1.0
4 S1.0
2 S1.0
3 S1.0
4 S1.0
5 S1.0
4'-5 1/2"
-1 1/2"
6 S1.0
5 S1.0
44'-11" E TYP.
14'-6 1/2"
22'-7 1/2"
82'-1"
N

1 FOUNDATION PLAN EXAMPLE

SCALE: 1/4" = 1'-0"

GUIDELINES AND KEYNOTES

A	COMPACTION REPORT OR PIER DETAILS IF REQUIRED
B	FOOTING LOCATION AND DETAILS
C	ADD ANY FOUNDATION NOTES: PLACEMENT OF ADDITIONAL REBAR/ENGINEERED POST TENSION CABLES
D	CROSS SECTION OF FOOTINGS/GRADE BEAMS (MINIMUM 4-#5 BARS IN FOOTINGS, MINIMUM 12"W x 18"D, MINIMUM 12" IN UNDISTURBED SOIL, MAT SPECS
E	SHOW EXTENTS OF CONCRETE AS WELL AS ANY BUILDING OFFSETS THAT MAY OCCUR
F	PROVIDE THE SCALE USED ON EACH PAGE OR EACH DRAWING IF VARIES


EXTEND SLAB TO FACE OF GRADE BEAM
SLOPE OUTSIDE GRADE AWAY FROM BUILDING
2" MAX.
FOR SLAB REINF. SEE PLAN
TOP OF SLAB 0'-0"
SEE PLAN
8" MIN.
1'-6"
3" CLR.
3" CLR.
(2) #5 CONT. TOP & BOTTOM W/ #3 TIES @ 24" O.C.
1'-0"
3'-0 1/2" @ SIM.

5 GRADE BEAM @ GRADE EXAMPLE

SCALE: 1" = 1'-0" F


2'-0"
SLOPE PAVING AWAY FROM BUILDING
1 1/2"
2" MAX.
FOR SLAB REINF. SEE PLAN
TOP OF SLAB 0'-0"
SEE PLAN
1'-6"
3" CLR.
3" CLR.
(2) #5 CONT. TOP & BOTTOM W/ #3 TIES @ 24" O.C.
1'-0"

6 GRADE BEAM @ OH DOOR EXAMPLE

SCALE: 1" = 1'-0"


2" MAX.
FOR SLAB REINF. SEE PLAN
TOP OF SLAB 0'-0"
SEE PLAN
1'-6" MIN.
3" CLR.
3" CLR.
(2) #5 CONT. TOP & BOTTOM W/ #3 TIES @ 24" O.C.
1'-0"

7 INTERIOR GRADE BEAM EXAMPLE

SCALE: 1" = 1'-0" F

CITY OF LONGVIEW STAMPS

COMPANY LOGO
OR OTHER

COMPANY NAME
COMPANY ADDRESS
ADDRESS LINE 2
COMPANY PHONE/FAX

PROFESSIONAL
SEAL IF REQUIRED

00/00/0000

PROJECT NAME
PROJECT ADDRESS
LONGVIEW, TEXAS

REVISIONS

NO.	DESCRIPTION	BY	DATE
1	FIRST REVISION DESCRIPTION	INTIAL	00/00/0000

FOUNDATION PLAN & DETAILS

PROJECT STATUS

JOB NO.: JOB NUMBER		ISSUE DATE: Issue Date	
DRAWN BY:	CHECKED BY:	APPROVED BY:	SCALE: As indicated
SHEET NO.: S1.0		REVISION NO.: 1	

Filename:F:\Land Development\2002\2002-094 Template Exhibits\CAD\STRUCTURAL\2002-094 - Structural.rvt